

Construction Update

Chambers Flat Road Upgrade

March 2024

SEE Civil is the appointed contractor to construct the 3.8 km Chambers Flat Road upgrade between Mount Lindesay Highway to just north of Kings Way.

Construction activities

Zone 1 – Ambulance Station to Norris Creek Road
Zone 2 – 1866 to 1737 Chambers Flat Road

With the traffic switch to the new westbound lane from Greenvale Road towards Munruben Ambulance Service in place, road reserve works move to the eastbound lane including:

- > building temporary access ramps from residential driveways to the live lane
- > clearing road reserve vegetation, stripping topsoil and installing drainage
- > bulk excavations, road foundation treatments and building gravel layers
- > constructing pavement including sealing and asphaltting
- > reinstating property fencing

Residents will be contacted to discuss arrangements to maintain property access (where possible) during the works.

Please note: Residents' bins within Zone 1 & 2 (northern side) will now be collected from the westbound lane. Residents requiring assistance moving their bin across are requested to contact SEE Civil's Community Relations Advisor.



logan.qld.gov.au

Zone 3 – Norris Creek Bridge

After extensive planning and preparation, the project has met a major milestone with the new Norris Creek Bridge taking shape.

At the end of February, a 500-tonne, all terrain crane was used over three days to lift 90 bridge girders into place.



To view timelapse video footage of the girder installation, captured on Council's Facebook site visit <https://fb.watch/qTAolgKEhi/>

The bridge's next stage of works includes:

- > pouring concrete approaches at each end of the bridge
- > constructing shared footpaths
- > installing bridge guardrails and kerbing

Nearby residents may experience noise and vibration with potential early morning starts, subject to the weather and construction conditions.

As concrete pours require specific temperatures, they are best completed during the cooler morning hours.



Zone 3 – Greenvale Road intersection upgrade

To upgrade Greenvale Road intersection, a sidetrack will connect Greenvale Road to the new western lane end of Norris Creek Bridge.

Residents of Greenvale Road will access the sidetrack as shown in diagram attached.

This will be controlled by temporary traffic signals for the safety of road users and staff.

Road users traveling west from Chambers Flat will access Greenvale Road via a left turn off the bridge.

Traffic exiting Greenvale Road will turn left only onto the western lane towards Mt Lindesay Highway.

The existing one-way sidetrack beside the bridge works from Grevillea Road to Greenvale Road will close when the Norris Creek Bridge opens to westbound traffic only.

The one-way diversion to Mt Lindesay Highway will remain to allow construction on the eastbound lane until the project is completed in late 2024.

Greenvale Road residents will receive further information about the upcoming traffic changes and impacts. Please check your letterbox or email regularly for updates.

Upgrading the intersection will provide safer turning and enhanced traffic flow.

What to expect

- > temporary traffic changes — reduced speed limits, assisted property access, traffic controls and direction of traffic to allow shifting of machinery and materials
- > frequent changes to lane and road alignments
- > odour during asphaltting and sealing works
- > increased truck movements
- > temporary property access changes
- > increased noise, dust and vibration
- > earlier start times for concrete pours at the bridge
- > weather and construction conditions may impact working hours



Zone 4 – 1545 Chambers Flat Road to Riverina Court

Zone 4 works are in the final stages including:

- > topsoil, landscaping and final driveway construction
- > road signage and line marking
- > fencing replacement
- > bus stop construction.

Working hours



Standard construction hours are Monday to Saturday 7 am to 6 pm (excluding Public Holidays)



Out-of-hours works

Residents and businesses will be notified ahead of time

Contact us

For more information about construction activities, contact SEE Civil's Community Relations Advisor

Phone: 0439 235 778

Email: info@SEECivil.com.au

Visit: logan.qld.gov.au/chambersflatroad

To subscribe for email updates please scan the QR code:



Greenvale Road temporary sidetrack

To upgrade the Greenvale Road intersection, a new sidetrack will connect Greenvale Road to the new western lane end of Norris Creek Bridge (see blue directional arrows).

This will be controlled by temporary traffic signals for the safety of road users and staff. **Traffic exiting Greenvale Road will only be able to turn left onto the western lane towards Mt Lindsay Highway.**

Road users traveling west from Chambers Flat will access Greenvale Road via a left turn off the bridge.

